



# Asansol Girls' College

(NAAC Accredited with 'A' Grade)  
(GOVT. SPONSORED)

Affiliated with The Kazi Nazrul University  
Dr. Anjali Roy Sarani, Asansol - 713304

Ph. 0341-2257107 (Day), 2254098 (Morn.), 2257600 (Principal), Fax : 0341-2257107

Website : www.agc.org.in • E-mail : mail@agc.org.in

Ref. No.....144/17.....

Date.....01.07.2017.....

Asansol Girls' College, Asansol-4


**Subject:** Cycle/ Motorbike Shed on south side of play ground attached to main college Building.

**Estimate Cost= Rs. 1,54,845.00**

Sealed quotation is invited for the above shed complete with supply & Construction and detailed as follows.

1. Size of the shed will be 11M long x4.5 M wide x2.8Mx3.4m high lean to shed with coloured corrugated steel sheets on roof, 400m wide skirting with sheeting in slopping side, 800m/m wide skirting on upper side, 400m/m x800m/m skirting on front and back side (i.e. East & West side).
2. 4nos M.S. Angle (ISA65x65x8) posts on slopping side and 4nos post on upper side. 65N.B. M.S. pipe main Rafter and 50N.B.pipe Purlins to be used. ISA50x50x6 bracings to be suitably provided in front and back side with one additional post as required.
3. Floor level will be 300m/m above G.L.
4. Flooring will be 150<sup>th</sup> P.C.C.(1:2:4) above F.B. Soling and sand filling as required.
5. 250<sup>th</sup> cement Brick shirting wall with plaster on all sides upto top of floor F.B. Soling.
6. Suitable Ramp to be provided on front side for easy entry for cycle.
7. All steel structure to be provided with 2coat paint over a coat of primer.
8. All posts to be embedded in 500x500x600 deep P.C.C.(M15) blocks with lugs as required.
9. All welded construction U.O.S.
10. All job to be done as per instruction of E.I.C./college Authority.
11. Some existing steel materials (Specially Pipes) are lying on back side of Mancha shed. Before quoting, contractors are requested to look into those matl and make use of them as free supply with due consideration during quoting of rates.
12. Contractors are requested to submit the quotation within 10 days from the date of this notice in the college office. Total price to be submitted with Ref No. of this letter.
13. All building matls, tools/tackle, labour, staging etc are within the scope of contractor. Quoted rates will be inclusive of all items including taxes duties etc.

Date:

  
Teacher-in-Charge  
Asansol Girls' College  
Teacher -in-Charge  
Asansol Girls' College