

Asansol Girls' College, Asansol – 4

Re: Open Garden in between Administration Building and Main College Building -

M.S. grid fencing around the Garden.

Proposed Estimated Cost= Rs. 219000.00 (for 135 M lg x 1.5 M high fencing)

Fencing will be in 3-4 parts. Each part will have few strands. Each strand is made of 40 N.B. M.S Tube (light) on either side which will be grouted with P.C.C (M-15) in ground. Top and bottom member will be 1SA 35 X 35 X 5. There will be one horizontal and one vertical member (F.S 25 X 6). Within this frame work there will be 2 ply 12 gauge galvanized wire mesh. Each strand will be aprox 3 m long X 1.5 m high (All-welded). Connection of one strand with the next strand will be made by welding with M.S flat at site. After complete erection total fencing will be painted with the anticorrosive paint over a coat of primer (Asian). Trial should be made to maintain the similarity of this new fencing with the existing M.S fencing in front of Admn.Building. Total length of fencing = 135 M, There will be 3 no.s gate (800 m/m wide) at suitable location as decided by College Authority.

Payment will be made for actual covered Area of fencing.

Sealed Quotation is invited for the above from experienced contractor having valid up-to-date Trade licence, I.T., P.T., EPF, ESI, & GST renewal certificate.

Copntractor is requested to fill up the following format and submit at the college office in a sealed envelop by 3 p.m of ^{29.11.}~~05.12.~~2019 and addressed to the Vice Principal, Asansol Girls' College with name, address and phone no. of the contractor.


Contd. Page 2 of 2

FORMAT OF QUOTATION FOR FENCING

Description of Job	Rate offered by contractor in Rs. Per Sq.m	Remarks
Fencing as per above specification complete with supply, fabrication, erection, painting etc. with necessary civil job.		

Date:.....

Signature of Contractor:


 21.11.19
 Vice Principal
 Asansol Girls' College
 Signature of Vice Principal
 Asansol Girls' College

Asansol Girls' College – Asansol-4

Re: Gate No:1- Repair & Renovation of Gate Man Cabin.

Sealed quotation is invited for the above job as per following format from experienced contractor.

The contractor is requested to fill up the following format and submit at the college office by 3 P.M. of ~~05.12.2019~~ 29.11.2019

Estimated Amount: Rs. 18923.00

Sl. No.	Description of Work	Quantity	Unit	Rate Rs.	Amount Rs.	Remarks.
1.	Removing worn out cement flooring and provide 25 th Art stone flooring in existing room and veranda.	18	Sq.M			
2.	1.5 th cement punning on new flooring & Skirting	18	Sq.M.			
3.	Removing worn out plaster and provide new cement sand plaster (1:6) on I/S and O/S of walls and ceiling 20 th (1:6)	60	Sq.M.			
4.	Scraping of wall, ceiling etc. and provide 2- coat white washing I/S, and O/S.	60	Sq.M.			
5.	Supply and install one 24'' wash basin with bracket and Down pipe. One ½ '' valve and 3 M long ½'' PVC water line from nearby existing water line for supply of water to wash basin.	As noted	-	L.S.		
Total Rs.....						

Please fill up and submit the format. In a sealed envelop with name, address and phone no.

Date:.....

Signature of Contractor:


Signature of Vice Principal.

Asansol Girls' College
Vice Principal
Asansol Girls' College

Asansol Girls' College – Asansol-4

Re: Stage attached to B.C.A. Building and facing play ground.

Structural frame work and wire mesh at U/S of existing steel roof trusses for protection against birds.

Sealed quotation is invited for the above job from experienced contractor having proper documents.

The contractor is requested to fill up the following format and submit at the college office by 3 p.m. of

~~05.12.2019~~ 29.11.2019

He must enclose one signed copy of this notice and self attested Xerox copies of all supporting documents.

Estimated Amount Rs. 53249.00.

Sl. No.	Description of Work	Quantity	Unit	Rate Rs.	Amount Rs.	Remarks.
1.	M.S. Structural work. Supply, fabrication, erection of Runner ISA 50 X 50 X6 @ 4.5 Kg / M.	216	Kg.			
2.	M.S. wire mesh – 3ply, 12 gange- Cut to shape and welded at U/S of frame work. Supply & erection.	228	Sq.M.			
3.	Supply & painting (2 coat) over a coat of primer to paint the above item No. 1 & 2.	228	Sq.M.			
4.	Repair of damaged concrete work of R.c.c. Gutter and replace M.S. Down pipe by equal dia P.V.C. pipe.	As noted	-	L.S.		

Total Rs.....

Please fill up and submit the format. In a sealed envelop with name, address and phone no.

Date:.....

Signature of Contractor :


Signature of Vice Principal.

Asansol Girls' College
Vice Principal
Asansol Girls' College